

December 16, 2004

HOLLY PARK  
LINDA HOFFER  
51700 LOVEJOY DR.  
MIDDLEBURY IN 46540

Re: Description: PREFABRICATED PLUMBING SYSTEM  
Manufacturer: HOLLY PARK  
Product Name: MANUFACTURED HOME  
Model Number(s): 805M  
Product File No: 20040555

The specifications and/or plans for this plumbing product have been reviewed and determined to be in compliance with chapters Comm 82 through 84, Wisconsin Administrative Code, and Chapters 145 and 160, Wisconsin Statutes.

The Department hereby issues an approval based on the Wisconsin Statutes and the Wisconsin Administrative Code. This approval is valid until the end of December 2009.

This approval is contingent upon compliance with the following stipulation(s):

- The flowing water supply pressure at the point(s) of connection must be at least 26 psig.
- The manufacturer must keep at the manufacturing plant a set of plans and specifications bearing the department's stamp of approval. The plans and specifications must be open to inspection by an authorized representative of the department.
- The maximum water supply fixture units (wsfu) on PEX tubing must not exceed 20.5 wsfu for 1-inch tubing, 11 wsfu for 3/4-inch tubing, 8 wsfu for 5/8-inch tubing, and 4 wsfu for 1/2-inch tubing.

A copy of the approved plans and/or specifications is enclosed.

The department is in no way endorsing this product or any advertising, and is not responsible for any situation which may result from its use.

Sincerely,

Michael J. Beckwith, CIPE  
Plumbing Product Reviewer  
phone: 608-266-6742  
fax: 608-267-9566  
e-mail: mike.beckwith@wi.gov