

Initial Elevator Inspection Guidelines

The following are items, which are required to be completed Prior to scheduling an Elevator Inspection

Completed	Applications and Plans are required to be approved Prior to commencing work. Approved plans shall be available on the job site.		
Completed	The hoistway shall be enclosed throughout its height by fire resistive construction as required by the Building Code. Machine room serving the hoistway shall be enclosed with the same fire resistive		
Completed	Froistwation f elevators and dumbwaiters penetrating more than three stories shall be provided with a means for venting smoke and hot gases to the outer air in case of fire. For exceptions see IBC Section 3004		
	The area of the vents shall not be less than 31/2 percent of the area of the hoistway nor less than 3 square feet (0.28 m2) for each elevator car, and not less than 31/2 percent nor less than 0.5 square foot (0.047 m2) for each dumbwaiter car in the hoistway, whichever is greater.		
	Of the total required vent area, not less than one-third shall be of the permanently open type unless all vents activate upon detection of smoke from any of the elevator lobby smoke detectors.		
Completed	Elevator pits are required to be designed so as to prevent the entry of ground water.		
Completed	A drain or sump pump complying with ss. 82.33 and 82.36 shall be provided in the pit. Connection of these drains and sumps to a sanitary system is prohibited.		
Completed	When sprinklers are installed in the hoistway all electrical equipment, located less than 1225 mm (48 in.) above the pit floor, shall be weatherproof (NEMA4); and wiring shall be identified for use in wet locations in accordance with the requirements in NFPA 70.		
Completed	Only machinery and equipment used in conjunction with the function or use of the elevator shall be permitted in the elevator machine room.		
Completed	Access to the machine room or penthouse for elevators shall not be through any toilet room, sleeping room or private room or space.		
Completed	Machine room door, lock, and closer. Identification signage.		
Completed	A clear path of not less than 450 mm (18 in.) shall be provided to all components that require maintenance. A clearance of not less than 450 mm (18 in.) shall be provided in the direction(s) required for maintenance access.		
Completed	Machine rooms shall be provided with natural or mechanical means to keep the ambient air temperature and humidity in the range specified by the elevator equipment manufacturer. Systems shall be installed as required by the Building Code.		
Completed	Sprinklers, where required by the Building Code, shall be installed in accordance with NFPA 13/13R.		
Completed	Smoke and Heat detection installed in accordance with NFPA 72. If sprinkler protection is provided heat detectors are required to activate the shunt trip circuit breaker prior to the application of water. Smoke and heat detection is not required in the elevator pit for those sprinklers installed within 2 feet of the pit floor.		
Completed	In any area in the pit, outside the refuge space, where the vertical clearance is less than 1100 mm (43 in.), that area shall be clearly marked on the pit floor. The marking shall consist of alternating 100 mm (4 in.) diagonal red and white stripes. All Electric Traction and Hydraulic elevators.		
Completed	For electric traction elevators any area outside the refuge space where the vertical clearance between the top of the car enclosure and the overhead structure or other obstructions is less than 1100 mm (43 in.), the top of the car enclosure shall be clearly marked.		
Completed	A standard railing shall be provided on the outside perimeter of the car top on all sides where the distance between the edges of the car top and the adjacent hoistway enclosure exceeds 300 mm (12 in.) horizontal clearance.		
Completed	All electric traction elevators except those whose empty car weight exceeds the total weight of the suspension ropes and counterweight, shall be provided with a device to prevent an ascending elevator from striking the hoistway overhead structure.		



Completed	All electric traction elevators shall be provided with a device that shall detect unintended car movement		
	away from the landing with the hoistway door not in the locked position and the car door not in the closed		
Completed	position. Emergency telephones shall be installed and programmed as required by ICC/ANSI A117.1		
Completed	The audible signaling device for elevators with a travel greater than 30 m (100 ft), shall be duplicated as		
	follows: one device shall be mounted on the car; a second device shall be placed at the designated level.		
Completed	Standby power shall be provided for elevators that are part of an accessible means of egress in accordance with IBC Section 1003.2.13.		
Completed	In buildings where a required accessible floor is four or more stories above or below a level of exit		
	discharge, at least one required accessible means of egress shall be an elevator complying with IBC Section 1003.2.13		
Completed	Standby power shall be installed where required by NEC Section 517 and the Building Code.		
Completed	The emergency or standby power system where provided, shall be capable of operating the elevator(s) with rated load, at least one at a time, unless otherwise required by the building code. The transfer between the normal and the emergency or standby power system shall be automatic.		
Completed	· · · · · · ·		
	alphabetical or numerical identification.		
Completed	Overspeed valves, where provided, shall be constructed, installed, and adjusted to ensure that the elevator		
	obtains the required performance. Field-adjustable overspeed valves shall be sealed after field setting.		
Completed	National Electrical Code requires 3 separate branch circuits. Car light circuit (overcurrent device shall be in		
	Machine Room), machine room light and receptacle, and the pit light and receptacle.		

Please note:

The department shall be notified when work that is covered by s. Comm. 18.1013 is complete and ready for an inspection to be scheduled. All test equipment on-site at the time the inspection is scheduled for. Any persons responsible for other systems used in connection with the elevator shall be present for the inspection. If the equipment is not complete and ready at the time of the scheduled inspection, the inspection will not be made and a cancellation fee will be assessed in accordance with ch. Comm. 2, and a reinspection will be scheduled

The installer shall sign this form and present it at the time of initial inspection.					
Installing Company.	Supervisor.	Date.			
If there are questions or concerns Please feel free to contact your local inspector					
David Holmes	Eau Claire	715-828-5901			
Tim Marty	Appleton	920-428-9422			
Jim Pacala	Woodruff	715-296-2906			
Jerry Rowell	Argyle	608-225-2108			
Dan Meneguin (Section Chief)	Madison	608-266-0056			
Larry Swaziek (Program Manager)	Madison	608-267-7701			
Brian Rausch (Plan Examiner)	Waukesha	262-521-5444			